

Scope of Works –

Making good on earthworks adjacent Car Park / Police station Flint Wall

Stage one

- To dig out area discussed including all root and muck away from site. – dig to be 100mm below tarmac level and back fill with MOT type 1 sub base, weed membrane and compact ready for Stage 2 .
- Taking note and being aware to avoid electric cables and any other utility services

Cost of Stage 1 - £740.00 +VAT

Stage Two (these are options to add to stage 1)

- Install Sleepers (Cost£430) – Base imbedded to below surface of the Car Park tarmac and to create an unbroken barrier / demarcation between Car Park tarmac and Earth Bedding area
- Supply Cotswold stone chippings 20mm £620.00 and fill between Sleepers and Flint wall to a level approx. one inch below surface of the Sleepers
- Ensure Sleepers are in keeping with the level of the Car park surface and secured in position
- Leave site clean, tidy and free from any debris associated with the works undertaken
- Leave site looking both aesthetically pleasing but also functionally robust, and as maintenance free as possible in the longer term

Cost of Stage 2 - £1000 +VAT

Total Cost £1,740 + VAT

Work to be undertaken over a two day period - Agreed as being 29th and 30th January

Parish Council to ensure Posters are displayed in and around the area in question leading up to works being undertaken informing residents that the Car Park will be closed for these two days, and the Contractor takes care to lock the Car Park barrier to enforce this measure to ensure Cars and Residents do not obstruct or are obstructed by the heavy machinery and other scope of works involved during the course of these works. And that all due care and attention is maintained to ensure the safety of Contractors and members of the public for the duration of the works.

The working area should be sectioned off from the public at all times.

The Contractor to have undertaken appropriate Risk assessments prior to undertaking the works and checking these with Parish Council Clerk before works commence